

A PDF of this newsletter and previous ones can be found by logging in to ServiceNet and clicking on the [Elsa Newsletter](#) section in the Technician References menu.

Audi
Truth in Engineering 

Audi Elsa Newsletter

Edition 103: September 15, 2014

Content

- [A.U.D.I. Search is Now Available through AccessAudi.com](#)
- [Technical Bulletins](#)
- [Pending Service Solutions](#)
- [Campaigns](#)
- [Updates](#)
- [Suggestions](#)



A.U.D.I. Search is Now Available through AccessAudi.com

A.U.D.I. Search, a Google-powered portal for searching selected repair information is now available as a direct link on [AccessAudi.com](#). Elsa users can now access A.U.D.I. Search by logging into [AccessAudi.com](#) and clicking the “**A.U.D.I. Search**” link under the “Service” category of related links:

Related Links

- + Academy CRC
 - + Audi connect
 - + Financial Services
 - + Marketing
 - + Parts
 - Service
-
- > Audi Care/VIN Lookup
 - > Audi Maintenance Calculator
 - > Audi Care Maintenance Contracts- e-Contracts
 - > Audi IQS Portal
 - > Audi Service Supplies eStore
 - > A.U.D.I. Search
 - > Audi Special Tools and Equipment
 - > Audi Top Service Process Guide

The new link will be in addition to the button available in the Technical Assistance section of Elsa.

Note: This link will only work for users with access to ElsaPro.

[Back to top](#)

Technical Bulletins

17 "Oil minimum warning, add one quart of oil" message appears, but oil level is above minimum (2038119/2)

Model(s)	Year	Vehicle Specific Equipment
A6, A7, S4, S5, S5 Cabriolet, Q7, Q5	2011-2014	3.0 FSI Engine

Condition:

- The message "Oil minimum warning, add one quart of oil" appears in the instrument cluster, but the oil level is above the minimum level (when measured with special tool T40178).
- There are no DTCs related to oil level stored in the ECM memory.

Production Solution: Updated oil level sensor.

91 MMI3G+ Navigation GPS location is inaccurate (MY13 only) (2036607/2)

Model(s)	Year	Vehicle Specific Equipment
A4, A5, A5 Cabriolet, A6, A7, Q5, Q7	2013-2015	MMI 3G+

Condition: The GPS location or vehicle direction indicated on the navigation map does not match the actual vehicle's location or actual direction of travel.

Production Solution: Implemented production solutions:

- Software change to ZUG K0715 improves GPS receiver firmware.
- Hardware change in MY14 improves GPS receiver clock hardware.

Pending production solution:

- Hardware change in MY15 to remove the HVAC blower effect on the GPS satellite reception. This change has not been implemented in production nor has it been implemented in any service parts.

[Back to top](#)

Pending Service Solutions

PSS 91 MMI 3G+ GPS location is inaccurate (MY13, MY14, & MY15) (2035919/4)		
Model(s)	Year	Vehicle Specific Equipment
A4, A5, A5 Cabriolet, A6, A7, Q5	2013-2015	MMI 3G+
Condition: The GPS location or vehicle direction indicated on the navigation map does not match the vehicle's actual location or direction of travel. Production Solution: Not applicable.		

Campaigns

No new campaigns this week.

Updates

No new updates this week.

Suggestions

Please send comments or suggestions to: aoa.workshopinformation@audi.com

[Back to top](#)

© 2014 Audi of America, Inc. All rights reserved. Information contained in this document is based on the latest information available at the time of printing and is subject to the copyright and other intellectual property rights of Audi of America, Inc., its affiliated companies and its licensors. All rights are reserved to make changes at any time without notice. No part of this document may be reproduced, stored in a retrieval system, or transmitted in any form or by any means, electronic, mechanical, photocopying, recording, or otherwise, nor may these materials be modified or reposted to other sites, without the prior expressed written permission of the publisher.