

## Latest Vehicle Concern Fixes

### POWERTRAIN



#### PHEV Stops Charging at 99%

#### 20MY Range Rover & RR Sport PHEV

##### Customer Voice:

- Vehicle stops charging at 99%.

##### Technical Description:

- When at high SOC the VSC requests less than 500W. At this point the BCCM switches off charging request and in most cases, charging will not resume.

##### Status:

- This will not affect normal drivability of the vehicle nor cause a MIL.
- Please address any HV System related DTCs that may disrupt the charging system first.
- If no other root cause is found, software is expected to be available 22-May

