

Latest Vehicle Concern Fixes

POWERTRAIN



AJ20P Hesitation from Wideband O2

19 & 20 MY Range Rover, RR Sport equipped with AJ20P6

Customer Voice:

- The vehicle has a hesitation when accelerating.
- There is a lack of power on acceleration.

Technical Description:

- There is a lack of power on acceleration. No DTCs related to the condition are stored.
- The complaint is resolved by replacement of the upstream (wideband) O2 sensor.

Status:

- Confirm there are no air leaks in the intake and exhaust prior to replacement of the O2 sensor
- Should the O2 sensor replacement resolve the complaint, raise an EPQR and include a session file and contact information for PRR.

