Technical Journal

TITLE:							
Polestar Bellow noise							
REF NO:	ISSUING DEPARTMENT:	CARM	ARKET:				
TJ 35811.1.0	Technical Service	United States and Canada					
	PARTNER:	ISSUE DATE:	STATUS DATE:				
	3 US 7515	2021-01-20	2021-02-22				
FUNC GROUP:	FUNC DESC:						
4620 Front axle casing		Page 1 of 5					

Attachment

File Name	File Size
TJI-520443-2_1_1_en-US.pdf	0.3236 MB

DESCRIPTION:

If a noise occurs from the front drive shaft bellows during slow driving and/or turning (e.g. parking maneuvers), follow the instructions under "service".

CSC Customer Symptom Codes

Code	Description
D2	Front/rear axle/Unusual noise

DTC Diagnostic Trouble Codes

Vehicle Type

Туре	Eng Desc	Sales	Body	Gear	Steer	Model Year	Plant	Chassis range	Struc Week Range
534						2021-9999	19	-	202007-999952

SERVICE:

Clean the bellows with a dry cloth and apply spray wax, Wurth part number 0892082500 on the bellows.

If possible, please perform this operation again 2 weeks after the first application.

Technical Journal 35811.1.0

Warranty claim info:

To get warranty claim accepted for a job described in this TJ, please use following data: VST OP number: 99922-2

VST Operation Number

VST Operation Number	Description		
99922-2	Boot, driveshaft constant velocity joint , outer		

LABOR TIME:

0.2

Labor time subject to change without notice.

VEHICLE REPORT:

Yes, please submit a Vehicle Report if the service solution described in this TJ has no effect. Use concern area "Vehicle Report Polestar" and sub concern area "Support not needed Polestar", use function group 4620.

To view TJ attachment continue to next page. This TJ has one attachment.

Polestar

Volvo Car Customer Service

TJ Instruction VCC-520443-2

Title	Boot, driveshaft constant velocity joint , outer	Page	1(3)
Action	Product fix	Operation number:	99922-2


Issue	Date	Reason
1	2020-01	First issue

Affected vehicles


Model yearModel2021, 2022Polestar 2

		Materials		
Materials	Qty.	Part No.	Notes	
Wax	0.1	30787812		

Color symbols



Cleaning



TJ Instruction VCC-520443-2

Page 3 (3)

