

TECHNICAL TOPICS

ELECTRICAL



Intermittent Passive Entry Operation

20-21MY L663 Defender

Customer Voice:

- Intermittently, the passive unlock feature does not work unless the smart key is in the customer's hand.

Technical Description:

- Due to poor signal strength the passive entry feature may not function intermittently

Status:

- **JLRTB02076NAS1** provides instructions to relocate a new RF Receiver behind the left D-pillar trim.
- Prior to installation a link lead will need to be assembled, please refer to TOPIX Workshop Manual section 418-02: Wiring Harnesses – Description & Operation Wiring Harness to review JLR approved wiring harness repair methods.
- Publication of JLRTB02076NAS1 was been delayed due to part availability.



PRINTED COPIES ARE UNCONTROLLED