



Volvo Chassis - Diagnostic Trouble Code (DTC) SA 0 FMI 0 or SPN 0 FMI 0 Present On Fault Code Readout - US10 And Newer Emissions, Model Year 2011 And Newer



> Internal Content

DTC SA 0 FMI 0 is caused by an aftermarket device installed on the datalink. Removal of this device and refreshing Tech Tool will render this code inactive or remove it outright. The device may be a hidden GPS tracking device, datalink analyzer, fuel management system, or electronic logs. If the device cannot be located, contact the owner or fleet for assistance.

Tags

[k42667415](#)

[sa 0 fmi 0](#)

[spn 0 fmi 0](#)

[volvo](#)

Related links and attachments

No links or attachments available



Feedback

[Give feedback](#)

to help improve the content of this article

Live UI