

<b>Reference</b>	SSM75802
<b>Models</b>	New Range Rover / L460 New Range Rover Sport / L461
<b>Title</b>	Deployable Side Step - No operation
<b>Category</b>	Accessories
<b>Last modified</b>	25-Jul-2022 00:00:00
<b>Symptom</b>	Electrical Accessories
<b>Content</b>	<p><u>Issue:</u> Customer states that the deployable side steps are not operational.</p> <p><u>Cause:</u> This has occurred after CCF As-Built has been loaded into the vehicle. Loading the CCF as-built has removed the Deployable Side Step option from the CCF.</p> <p><u>Action:</u> Please follow step 8 completely in the accessory fitting instructions for Deployable Side Steps (Electrical Only) only after all other CCF work has been completed.</p> <p><small>anEhdHRlcnM7MjAyMl0wNy0yNVQxNzo1NjowMy44OTdaOzEzNi4yMjYyNTUuMTEwOw==</small></p>