

BODY/CHASSIS – RED SUSPENSION WARNING LIGHT IN CLUSTER

22-23MY Range Rover, 23my RR Sport

Customer Voice:

- A customer may report that the red suspension warning light is illuminated on the instrument cluster.

Technical Description:

- A technician may find DTC U3000-47 stored in the CHCM. This may be due to the CHCM performing an internal reset after engine start up.

Status:

- The issue can be recovered by an ignition cycle.
- Root cause is under investigation.
- **SSM 76008** has been published to provide repair guidance.
- Please do not replace the CHCM, unless instructed to do so.

