

SERVICE BULLETIN

SB2434

ADDRESSEES: Owners and operators

VEHICLE MODEL : CX45 E, TDX25 E

MANUAL CHAPTER : 13.05 Compressed-air supply – Compressor

BULLETIN TYPE : Service information

DATE : February 23rd, 2024

SUBJECT : Shortened replacement interval for air filter of "Atlas

Copco SFR4" air compressor

CONDITIONS: This service bulletin does not entitle to any reimbursement.

APPLICATION

This service bulletin is applicable to the following vehicles:

Vehicle model	Vehicle identification number	
CX45 E	82000 → 82048	
TDX25 E	89501 → 89557	

INTRODUCTION

Field reports have shown that the air filter element (VH11692512) of the air compressor needs to be renewed more frequently. Where previously an interval of 3000 operating hours was determined for the replacement of the filter element, the interval is now shortened to 1500 operating hours (or yearly, whichever comes first).




Figure 1: "Atlas Copco SFR4" air compressor

REPLACEMENT INTERVAL FOR AIR-FILTER ELEMENT

Action	Current interval	New interval
To change air-filter element*	3000 hours	1500 hours (or yearly, whichever comes first)

^{*}The air-filter element must also be renewed if the intermediate check shows that the element is heavy contaminated. For the interval of the intermediate check, refer to chapter 1.1 in the maintenance manual.

Continued on next page.

LOCATION OF HOUR COUNTER

CX45E: in junction box EKVTDX25E: in junction box EK2




Figure 2: Hour counter (position on CX45 shown)

HELP DESK

If there are any questions, please call ABC Customer Care & Parts Source toll-free for guidance on 1-877-427-7278. Listen for the prompts for warranty and select that option.

DISCLAIMER

The procedures contained herein are not exclusive. Van Hool cannot possibly know, evaluate, or advise the transportation industry of all conceivable ways in which a procedure may be undertaken or of the possible consequences of each such procedure. Other procedures may be as good, or better, depending upon the particular circumstances involved. Each carrier who uses the procedures herein must first satisfy itself thoroughly that neither the safety of its employees or agents, nor the safety or usefulness of any products, will be jeopardized by any procedure selected.

INFORMATION HANDLING:

Important additions and modifications regarding technical information not yet included in the manual will be communicated through Service Bulletins.

VAN HOOL CUSTOMER PORTAL:

Consult the customer portal regularly for the latest service documentation. In addition to the maintenance manual, you will also find the operating manual and the spare parts catalogue of your vehicle on the customer portal. The customer portal is accessible through www.vanhool.be, and only with a code (password) from Van Hool. If you do not have a password yet, request it by using the link on the Van Hool website.