

This TSB supersedes TSB 19-AT-012G to add G80 (RG3), GV70 (JK1), GV80 (JX1).

DESCRIPTION: This TSB provides a procedure to diagnose and repair a transmission for the following Incorrect Ratio DTC (transmission clutch slipping more than 200 rpm in gear).

DTC	DESCRIPTION
P073100	Gear 1 incorrect ratio
P073200	Gear 2 incorrect ratio
P073300	Gear 3 incorrect ratio
P073400	Gear 4 incorrect ratio
P073500	Gear 5 incorrect ratio
P072900	Gear 6 incorrect ratio
P076F00	Gear 7 incorrect ratio
P073000	Gear 8 incorrect ratio

APPLICABLE VEHICLES:

2019~	G70 (IK)	2019~	G90 (HI)
2019~20	G80 (DH)	2021~	GV80 (JX1)
2021~	G80 (RG3)	2022~	GV70 (JK1)

WARRANTY INFORMATION: Normal Warranty applies

SERVICE PROCEDURE:

- 1. Connect a GDS and check for DTC. Record the DTC and delete the DTC.
 - If any solenoid DTC are found, refer to TSB 21-AT-003G or shop manual and follow the repair procedure.
 - If no solenoid DTC are found, refer to the appropriate shop manual, Automatic Transmission section and replace the transmission.

NOTE: A Prior Approval (PA) request will need to submitted prior to performing the repair.