
Reference	SSM72201
Models	XJ / X351
Title	X351 Side Rear Window Electric Sunblind (LWB Only)
Category	Body
Last modified	08-Feb-2016 00:00:00
Symptom	102000 Window/Glass
Attachments	1SSM Attachment Example.pdf (1SSM Attachment Example.pdf)
Content	<p>Issue: JLR engineering are currently receiving a number of EPQR's regarding X351 rear door electric sunblind's not operating at PDI or following battery disconnect causing the loss of the single press function and also the sunblind material will appear distorted on the front edge. Please view example PDF attachment.</p> <p>Cause: Rear door sunblind module is not Initialized at PDI or the module has lost the power feed/earth feed.</p> <p>Action: Please carry out rear sunblind Initialization (Topix section 501-05) or using the SDD service functions sunblind Initialization routine.</p> <p>PLEASE NOTE – The rear windows must be initialized before the sunblind Initialization routine as this will cause the routine to fail.</p>



